



OVERHEAD SERVICE

NOTES:

- 1. CONSTRUCTION SHALL CONFORM TO THESE REQUIREMENTS EXCEPT AS OTHERWISE DIRECTED BY THE COUNTY ENGINEER.
- 2. CONTRACTOR SHALL INSTALL #5/5(T) PULL BOX OR UTILITY VAULT PER SERVING UTILITY REQUIREMENTS, 3" SERVICE CONDUIT, AND 2" CONDUIT AND CONDUCTORS FROM EQUIPMENT TO PULL BOX.
- 3. CONDUIT AND CONDUCTOR TO ENTER PULL BOX THROUGH BOTTOM OF BOX. PULL BOXES SHALL BE PARALLEL WITH THE ROADWAY.
- 4. SEE COUNTY DRAWING NO. 600, NOTE NO. 3
 TO DETERMINE IF A #5 OR 5(T) PULL BOX IS
 REQUIRED. ALSO CHECK PLANS AND NOTES.

COUNTY OF SONOMA

DEPARTMENT OF TRANSPORTATION

AND PUBLIC WORKS

ELECTRIC SERVICE DETAIL OVERHEAD SERVICE

APPROVED BY: SCALE: DRAWING NO. NONE 608